



G-STRUT 4100 13th Street SW, Canton OH 44710

Phone: 866.997.8788 – Fax: 330.477.0626

www.gregorystrut.com

PART #	FIGURE NO.	PIPE SIZE	ACTUAL THICKNESS OF COVERING	HANGER ROLLER SIZE		CENTER LINE OF PIPE TO CENTER LINE OF SADDLE (C)	CENTER LINE OF PIPE TO CENTER LINE OF ROLLER (D)	MAXIMUM RECOMMENDED LOAD(lbs.)	LBS./ 100pcs
				series 630	series 610				
W570166	66	14	1-1/2	16	18	8-7/8	10-3/16	5000	767
W570167	67	14	2	16	18	9-1/4	10-3/4	5000	943
W570168	68	14	2-1/2	18	20	9-3/4	11-5/16	5000	969
W570169	69	14	3	18	20	10-1/4	11-7/8	5000	1182
W570170	70	14	4	20	-	11-7/16	13-1/8	7200	1848
W570171	71	16	1-1/2	18	20	9-7/8	11-3/8	5000	835
W570172	72	16	2	18	20	10-1/4	11-7/8	5000	1000
W570173	73	16	2-1/2	20	-	10-7/8	12-7/16	7200	1462
W570174	74	16	3	24	-	11-3/16	13-1/18	7200	1817
W570175	75	16	4	24	-	12-5/16	14-3/16	7200	2180
W570176	76	18	1-1/2	20	-	10-7/8	12-1/2	5000	892
W570177	77	18	2	20	-	11-1/2	13-1/16	7200	1319
W570178	78	18	2-1/2	24	-	12	13-5/16	7200	1689
W750179	79	18	3	24	-	12-5/16	14-1/4	7200	1820
W570180	80	18	4	24	-	13-1/2	15/7/16	7200	2195
W570181	81	20	1-1/2	24	-	11-3/4	13-11/16	7200	1376
W570182	82	20	2	24	-	2-5/16	14-1/4	7200	1498
W570183	83	20	2-1/2	24	-	12-7/8	14-13/16	7200	1679
W570184	84	20	3	24	-	13-1/2	15-1/2	7200	1840
W570185	85	20	4	30	-	14-3/16	16-5/8	7200	2283
W570186	86	24	1-1/2	30	-	13-5/8	16-1/16	7200	1605

PROJECT INFORMATION	APPROVAL STAMP
Project:	Notes:
Address:	
Contractor:	
Engineer:	
Date:	
Approved <input type="checkbox"/> Approved as Noted <input type="checkbox"/> Not Approved <input type="checkbox"/>	